

**Monorail –PIU, MMRDA, Wadala Monorail Depot, Next to Anik Bus
Depot, Wadala (E)- 400 037.**

-:Draft:-

Notice Inviting the Quotation

**Name of Work:- Providing, Supplying, laying and fixing material for Re-instate of
Mumbai Municipal Corporation water supply to the wadala monorail
depot and wadala station of Mumbai Monorail.**

This is to inform you that, Monorail-PIU, MMRDA, Mumbai is inviting the sealed quotation for the above-said work at Mumbai Monorail, Wadala Depot. The details of work as follows;

Sr. No	Work Description	Unit	Area	Rate per unit	Amount (Rs.)
1	Providing & Supplying, loading, transporting on site, unloading, lowering in trenches, assembling and jointing Ductile Iron 80 mm pipes (K-9) including chamfering cut edges of pipes and specials and fixing with Styrene Butadiene Rubber (SBR) Ring Gaskets for following diameters (Tyton joint pipes). The pipe shall confirm IS : 8329 & SBR Ring Gasket shall confirm IS : 5382 & IS : 12820. The rate is inclusive of cleaning, flushing & testing of water mains upto 6 kg/sq.cm etc complete in all respect and as directed by Engineer in Charge (Pipe shall be coated with cement mortar lining from inside and zinc coating followed by bitumen coating from outside as specified).	Rmt	593		
2	Supplying, providing, laying and jointing 20 mm GI pipes in trenches of following class and diameter by wrapping them by hessian cloth with tar coating and including any nominal pipe length required to be laid above ground level, conveyance from stores to site work, all labour, necessary excavation, backfilling, giving satisfactory hydraulic test, etc complete in all respect as directed by Engineer in Charge. Note : Only MCGM approved GI pipe brands shall be used	Rmt	435		
3	Sluice Valve - Providing and fixing (class II) C.I. sluice valves (with cap) complete with bolts, nuts, rubber insertions etc. (the tail pieces if required will be paid separately) :100 mm diameter	Nos	1		
				GST@.....%	
				Total amount (Rs.)	

Terms and conditions;

1. The material will be supplied by the bidder shall be followed the standard specification as mentioned in the above table.
2. The work will be carried out by taking all the safety measures.
3. The bidder is bound to follow the rules and regulations of MMRDA.
4. The payment will be made as per the due procedure of MMRDA.
5. The time limit to complete the work will be 30 days after issuing the Work order.
6. The MMRDA will not provide any Transportation Facility to load and unload the material at the site.
7. The work will be carried out on supervision of officials of MMRDA.
8. The test report of the materil should be obtained from ISO and government approved laboratory.
9. The bidder should give the warranty certificate of the materil supplied, laid at Monorai project.
10. The quotation must be in sealed format.
11. The last date of submission of quotation is 22.07.2021

Date :- 16.07.2021

**sd/-
(C.E.Bansode)
Transportation Engineer-Infra
Monorail-PIU.**